

Project: Ybarra Academy – Drop-off Driveway Asphalt Replacement

Location: 1300 Brea Canyon Cut-Off Road, Walnut, CA 91789

General Description/Scope of Work:

Drop-Off Driveway - Option # 1

- *Remove and dispose of approximately 7,600 square feet of existing asphalt.*
- *Grade & compact area to receive 4" AC over 6" of compacted Class II CMB. Haul-off excess dirt.*
- *Install approximately 200 linear feet of 4" wide concrete mow curb, where new asphalt paving meets edge of turf.*
- *Construct 4" AC over 6" of compacted Class II CMB*
- *Stripe driveway as needed.*
- *Seal-coat & restripe new asphalt surface, 30 days following initial installation.*

Drop-Off Driveway - Option # 2

- *Pulverize (recycle) existing asphalt and use in lieu of Class II CMB. Haul away excess dirt and surplus pulverized asphalt; all else remains the same as Option #1, above.*

Notes:

Dimensions and quantities indicated above are for reference ONLY. Contractors bidding said project are responsible for field verifying all dimensions and quantities shown.