

Project: Northam Elementary Playground - Asphalt Replacement

Location: 17800 East Renault Street, La Puente, CA 91744

General Description/Scope of Work:

Playground - Option # 1

- *Remove and dispose of approximately 37,500 square feet of existing asphalt.*
- *Remove and dispose of approximately 400 linear feet of existing redwood 2 x 4 headers.*
- *Grade & compact area to receive 3" AC over 4" of compacted Class II CMB. Haul-off excess dirt.*
- *Install approximately 400 linear feet of 2"x 4" redwood header, where new asphalt paving meets edge of turf.*
- *Construct 3" AC over 4" of compacted Class II CMB*
- *Stripe playground as needed.*
- *Seal-coat & restripe new asphalt surface, 30 days following initial installation.*

Playground - Option # 2

- *Pulverize (recycle) existing asphalt and use in lieu of Class II CMB. Haul away excess dirt and surplus pulverized asphalt; all else remains the same as Option #1, above.*

Notes:

Dimensions and quantities indicated above are for reference ONLY. Contractors bidding said project are responsible for field verifying all dimensions and quantities shown.