

Rowland Unified School District

Rowland High School

Scope of work for fence replacement

Scope of work:

Replace approx. 1,215' X 8' tall existing chain link fencing with 8 gauge black vinyl coated chain link fence with 1" mesh openings.

Replace approx. 1,478' X 6' tall' existing chain link fencing with 8 gauge black vinyl coated chain link fencing with 1" mesh openings.

Replace existing chain link fencing on 17 gates on the Southwest side of Otterbein Ave. and around Valencia to the East and North.

See attached installation diagram for gate # and size of gates

- 1) Remove and dispose of existing chain link fencing approx. 2693 linear ft. and chain link fencing on all 17 gates.
- 2) Straighten out all posts as determined by owner
- 3) Adjust or replace top rails as determined by owner
- 4) Paint all post, rails and gate posts/frames with black galvanized paint
- 5) Install all new bottom tension wire black vinyl coated.
- 6) Replace all tension bars, tension bands, and brace bands. All to be painted black by contractor.

Chain link Wire will be an 11 gauge core coated with black vinyl creating an 8 gauge finish on the 1,215' X 8' with 1" Mesh

Chain Link Wire will be 11 gauge core coated with black vinyl creating and 8 gauge finish on the 1,478' X 6' with 1" Mesh

All work to be completed according to standard practices, any alterations or deviations from the above specifications involving extra cost must be in writing to Danny Romo.

All work to be completed within 30 calendar days from the day from Notice to proceed,

Any questions please call Danny Romo (626) 712-7279

email dromo@rowlandschools.org

