

**Project: Telesis Academy – Paving Project**

**Location: 2800 East Hollingworth Street, West Covina, CA 91792**

**General Description/Scope of Work:**

**Main Playground (South):**

- Four (4) existing light poles & caissons are to remain. Contractor is to protect caissons and light posts against damage.
- Nine (9) existing basketball posts with backboards (3 double & 6 singles) are to remain. Contractor is to protect concrete apron against damage.
- Four (4) 5' x 15' existing aluminum bleachers will be removed, store and reinstalled by the District
- *Remove and dispose of 8 volley-ball posts & footings. Contractor is to record & mark location of volley-ball posts for future installation of replacement post by others.*
- *Remove and dispose of any existing wood headers.*
- *Remove and dispose of approximately 52,000 square feet of existing asphalt paving (actual thickness of asphalt is unknown). **\*Asphalt contains Petromat\****
  
- Grade and compact area to be paved for proper drainage and to receive 3" of ½" aggregate, hot-mix-asphalt [HMA] paving over 3" of properly compacted CMB.
- Contractor is to haul-off & dispose of any excess dirt and/or project related rubble and debris.
- Install 2"x 4" or 2" x 6" redwood header, where needed.
- Place 3" of compacted CMB and finish grade as required.
- Place 3" of ½" aggregate, hot-mix-asphalt [HMA] paving over finish graded and compacted CMB.
- Stripe playground as needed.
- Seal-coat & restripe new asphalt surface, 30 days following initial installation.

**Center Playground (North):**

- *Remove and dispose of approximately 7,700 square feet of existing asphalt paving (actual thickness of asphalt is unknown). **\*Asphalt contains Petromat\****

- Grade and compact areas to be paved for proper drainage and to receive 3" of ½" aggregate, hot-mix-asphalt [HMA] paving over 3" of properly compacted CMB.
- Contractor is to haul-off & dispose of any excess dirt and/or project related rubble and debris.
- Place 3" of compacted CMB and finish grade as required.
- Place 3" of ½" aggregate, hot-mix-asphalt [HMA] paving over finish graded and compacted CMB.
- Stripe playground as needed.
- Seal-coat & restripe new asphalt surface, 30 days following initial installation.

**Notes:**

***Dimensions and quantities indicated above are for reference ONLY.  
Contractors bidding this project are responsible for field verifying all  
dimensions and quantities shown.***